



**FRIENDS OF PATAPSCO VALLEY STATE PARK
REQUEST FOR BIDS FOR
TRAILHEAD KIOSKS AND TRAIL SIGNAGE AT PATAPSCO VALLEY STATE
PARK**

Key Information Summary Chart:

Invitation for Bids	Trailhead Kiosks and Trail Signage at Patapsco Valley State Park
RFP Issue Date:	5.20.20
RFP Issuing Office:	Friends of Patapsco Valley State Park
Proposals are to be sent to:	Dave Ferraro, 8020 Baltimore National Pike, Ellicott City, MD 21043 email: director@fpvsp.org
Proposal Due (Closing) Date and Time:	6.1.2020
Pre-Proposal Conference:	N/A
Site Visit	By appointment, please contact via email: director@fpvsp.org
Contract Duration:	7.1.20 - 9.1.20
Primary Place of Performance:	Patapsco Valley State Park



**FRIENDS OF PATAPSCO VALLEY STATE PARK
REQUEST FOR BIDS FOR
TRAILHEAD KIOSKS AND TRAIL SIGNAGE AT PATAPSCO VALLEY STATE
PARK**

FRIENDS OF PATAPSCO VALLEY STATE PARK, is soliciting bids for Trailhead Kiosks and Trail Signage at Patapsco Valley State Park

Please read the instructions and submit bids based on the information contained on this sheet. The attached Bid Proposal sheet shall be filled out completely and submitted with the bid.

General Instructions:

This invitation for bids is for the purchase of the following:

Purchase of all materials, fabrication and installation of 10 kiosks as described in the attached construction drawing "PVSP Kiosk Drawings". (Please note there are two sizes of kiosks, large and small and this bid shall install 5 large and 5 small kiosks)

Contractor will install the kiosks and bike fixit stations at locations described in the attached document "Kiosk and Bike Fixit Station Map".

SCOPE OF WORK:

- Purchase all materials, fabricate and install 10 trailhead kiosks
- Purchase and install 4 Dero bike fixit stations, including all necessary installation materials
- Remove all installation materials, clean and level each kiosk/station site
- Coordinate installation with FPVSP to facilitate access to installation sites and for photography/documentation of project
- Coordinate "sign off" with FPVSP on each completed installation
- Installation is to occur 7.1.20 - 9.1.20

FRIENDS OF PATAPSCO VALLEY STATE PARK RESERVES THE RIGHT TO ACCEPT/REJECT ANY OR ALL BIDS.



**FRIENDS OF PATAPSCO VALLEY STATE PARK
 BID SUBMITTAL SHEET**

RT#2022

PROJECT ELEMENTS AND COSTS

Item #	Description	Qty	Unit Price	Total Cost
1	6"x6"x12'6" pressure treated lumber (support posts)	20		
2	4"x6"x 4'6" pressure treated lumber	40		
3	4"x6"x 5' pressure treated lumber (rafters)	20		
4	4"x6"x 6'4" pressure treated lumber (horizontal beams, large kiosks)	10		
5	4"x6"x 4'4" pressure treated lumber (horizontal beams, small kiosks)	10		
6	6'x4'x1/4" Lexan (large kiosks)	5		
7	4'x4'x1/4" Lexan (small kiosks)	5		
8	2"x2"x4' pressure treated board (panel frames, small kiosks/larges kiosks)	30		
9	2"x2"x6' pressure treated board (panel frames, small kiosks/larges kiosks)	10		
10	15" (minimum) x10' aluminum ridge flashing	10		
11	2"x4" pressure treated boards, (roof frame)	180		
12	Roof tiles (as needed, approx. 100 sq.ft for large kiosk)	5		
13	Roof tiles (as needed, approx. 75 sq.ft for small kiosk)	5		
14	1/2" x 10" lag screws	120		
15	1/4" x 8" lag screws (panel frame)	180		
16	1/2" x 8" lag screws	80		
17	Galvanized nails to attach 2"x4" roof frame	As needed		
18	Galvanized nails to attach roof tiles	As needed		
19	60 pound bags of ready mix concrete (for kiosks)	120		
20	60 pound bags of ready mix concrete (for bike fixit stations)	12		
21	Dero bike fixit stations	4		
22	Misc. fabrication/installation materials	As needed		
22	Labor			
	Total Cost			

Total Cost _____

Bidders Name: _____

Address: _____

Telephone: _____

Fax: _____

Signature: _____

Date: _____